

ANNEX 'F' TO

MINI S-1000 Rev. 30NU/SC/105-005

Page 4

Issued with AL 2

101.0

INSTRUCTIONS

CAPACITOR TESTING

OP

- 2414.
1.
 - a. Test both suppressor capacitors item (1) in situ using Wayne Kerr Component Bridge CT 375 (ST 26)
 - b. Connect ST22 red cable to terminal 7 or input pin 1 and black cable to frame; balance bridge for two terminal network.
 - c. Capacitance to be $1.2 \mu\text{f}$ to $1.8 \mu\text{f}$ ($1.5 \mu\text{f} \pm 20\%$).