

CHAP. 4 AIRFRAME S.P. 411 A.L. 1 SHEET 1 OF 2	SERVICING PROCEDURE F53 T55	BAC F53 & T55 (SA) 5A3A Section 1 2nd Edition
Mainplane Fuel Tanks - Examination For Leaks.	AFSC 42450 42470 43151 43171 43250	TIME EST
Safety and Servicing Notes are to be complied with throughout the work detailed on this card.		
SPECIAL TOOLS AND EQUIPMENT Nil.		ASSOCIATED PROCEDURES SP 1 (P) 2 (P)
<u>42450 / 43151</u>		
1. PREPARATION		
1.1 Mainplane fuel tanks.	Ensure full.	
1.2 No.1 ECU.	Remove (SP 1 (P)), (43250).	
2. EXAMINATION		
2.1 No.1 engine compartment roof.	Look for signs of fuel seepage, particularly around bolt heads and joints in heat shield.	
2.2 Rear main attachment brackets at Frame 42.	Examine for signs of fuel seepage.	
NOTE: Item 3 is applicable only if signs of fuel seepage are visible in the areas detailed in Item 2.		
3. RECTIFICATION		
3.1 Heat shield.	Remove.	
3.2 Fuel tanks.	(i) Locate fuel leak. (ii) Repair in accordance with Repair Scheme SRO/20/57.	
	NOTE: The applicable drawings are available from British Aerospace, Saudi Technical Support Dept., Warton, Lancashire, England.	
Continued Overleaf		

CHAP. 4 AIRFRAME

S.P. 411 A.L.

SHEET 2 OF 2

SERVICING PROCEDURE

F53 T55

BAC F53 & T55 (SA)

5A3A Section 1

2nd Edition

Safety and Servicing Notes are to be complied with  
throughout the work detailed on this card.

43250

4. GENERAL

4.1 No.1 ECU.

Refit (SP 2 (P)).

42470 / 43171

5. INSPECTION STAGE

5.1 Inspect.

Item 4, if applicable.

This file was downloaded  
from the RTFM Library.

Link: [www.scottbouch.com/rtfm](http://www.scottbouch.com/rtfm)

Please see site for usage terms,  
and more aircraft documents.

