# Chapter 16

# **RESISTOR UNIT, ROTAX, TYPE ZA8301**

## LIST OF CONTENTS

Para.									Para.	
Introduction	•••	•••	•••	• • •	1	Installation	•••	•••	•••	5
Description	•••	•••		•••	2	Servicing	•••		•••	6
Operation	•••	•••	•••	•••	3	Insulation resistance	test	•••	•••	7
Electrical conn	ections				4					

## LIST OF ILLUSTRATIONS

Resistor unit, Type ZA 8301 ... Fig. 1

## LEADING PARTICULARS

Resistor unit,	301	•••	•••	Ref. No. 5CZ/5929						
Resistance of ele	•••	•••	• • •	•••	0	·013-(	0·017 ohms			
Current loading	•••	•••	•••	•••	•••	•••	•••	220 amp.		
Overall dimensions—										
Height	•••	•••		•••	***	•••		3.421 in.		
Length	•••		•••	•••	•••	•••	•••	5.270 in.		
Width	•••	•••	•••	•••	•••	•••	•••	2.800 in.		
Weight	•••	•••	•••	•••	•••	•••	1	lb. 2.5 oz.		

#### Introduction

1. The ZA 8301 resistor unit has been designed for use in conjunction with Rotax starter, Type C 10501, its purpose being to limit the armature current at the outset of the starting cycle.

## DESCRIPTION

2. The unit (fig. 1) comprises a resistor element formed from folded "Brightray" strip which is mounted in four "Micalex" insulated clamp brackets. The resistance of the element is 0.015 ohm.

## Operation

3. When the starter button is pressed, a time switch diverts the current from the main supply through the resistor unit to the starter. After a period of two seconds, the time switch operates and the starting current, limited by the resistor element, then flows for a further

twenty-eight seconds after which the time switch operates again to short the resistor unit out of the circuit.




Fig. 1. Resistor unit, Type ZA 8301

## Electrical connections

4. Electrical connections are made via two 0.250 in. B.S.F. studs.

## INSTALLATION

5. For installation purposes, four clearance slots 0.156 in. x 0.250 in. for 0.142 in. fixing screws are drilled in the feet of the insulated clamp brackets, the centres of the holes forming a rectangle 2.750 in. x 2.250 in. nominal centres respectively.

#### SERVICING

6. Check that all connections are tight and mating surfaces clean.

## Insulation resistance test

7. Check the insulation resistance between all live parts and the frame, using a 250-volt insulation resistance tester; the insulation resistance should not be less than 0.5 megohm (for R.N.) or 5 megohms (for R.A.F.).